



HEADER CURB NOTES:

1. HEADER CURBS SHALL BE 3,000 PSI CONCRETE STRENGTH.
2. HEADER CURBS HAND POURED AND PLACED SHALL INCLUDE:
 - (a) 2 CONTINUOUS #4 REBARS.
 - (b) WITH 1/2 INCH EXPANSION JOINTS EVERY 20.0 FEET AND CONTROL JOINTS EVERY 5.0 FEET, AND A BROOM FINISH.
3. HEADER CURBS MACHINE INSTALLED SHALL INCLUDE:
 - (a) 2.0 POUNDS OF LONG FIBERGLASS MESH CUBIC YARD.
 - (b) WITH 1/2 INCH EXPANSION JOINTS EVERY 20.0 FEET AND CONTROL JOINTS EVERY 5.0 FEET, AND A BROOM FINISH.

DETAIL NO.

108



CITY OF EL PASO
PARKS & RECREATION

DETAIL NAME

HEADER CURB

NTS